

VP-1	FAN SPEED	X						X	X
VP-1	VELOCITY PRESSURE (CFM)			X				X	X

2.2.3.	AFTER A 10 SECOND DELAY FROM THE FAN OFF-CONFIRMATION SIGNALS, THE OUTSIDE AIR AND EXHAUST AIR ISOLATION DAMPERS SHALL BE COMMANDED CLOSED AND PROVEN VIA THE "CLOSED" END SWITCHES.	VELOCITY SIGNALS. THESE SIGNALS SHALL BE USED TO CALCULATE AND DISPLAY THE OUTDOOR AIR AMOUNTS.
2.2.4.	WHILE STOPPED, IF THE TEMPERATURE INSIDE THE UNIT DROPS	12. RELEAF AIR CONTROL

12.1. EACH GENERAL EXHAUST DUCT AT EACH FLOOR IS EQUIPPED WITH A MOTORIZED DAMPER THAT MODULATES TO MAINTAIN A FLOOR PRESSURE SENSOR AT 0.05" WG POSITIVE PRESSURE.

14.11. EXCESS BTU AND FAN ENERGY
REMOVED



COMMANDED OFF BUT STAYS ON (ADJ.)

COMMANDED OFF BUT STAYS ON (ADJ.)

SHILBERG LEVINAS

Shilberg Levinas 5101 Wisconsin Ave #310 T 202.244.5101
Architectural Design Inc. Arlington, DC 20016 F 202.244.5363

Logos and drawings are protected by copyright, and may not be reused, copied or reproduced without the expressed written consent of the entity above.

Copyright © 2023 ShilbergLevinas Architectural Design Inc.
All rights reserved worldwide

OWNER
DISTRICT OF COLUMBIA
DC DEPARTMENT OF GENERAL SERVICES (DGS)
DC PUBLIC SCHOOLS (DCPS)

LANDSCAPE ARCHITECT
BRADLEY SITE DESIGN
1010 WISCONSIN AVE NW, #208
WASHINGTON, DC 20007

MEP+FP ENGINEER

GLOBAL ENGINEERING SOLUTIONS OF WASHINGTON DC (GES)
4400 JENNIFER ST NW #240

KITCHEN / FOOD SERVICE

NYIKOS-GARCIA FOODSERVICE DESIGN

(410) 300-036

ISSUES

SEAL

DATE:	06/06/2025
SCALE:	1/8" = 1'-0"

Abstract

M502B